

NUMBER OF ASSEMBLIES TO BE INSTALLED;

BOC TO BOC 24' OR LESS IN WIDTH = 3

BOC TO BOC 25'-32' IN WIDTH = 4


BOC TO BOC 33'-40' IN WIDTH = 5

BOC TO BOC 41'-48' IN WIDTH = 6

BOC TO BOC 49'-56' IN WIDTH = 7

BOC TO BOC 57'-64' IN WIDTH = 8

BOC = BACK OF CURB. FOR OPEN DITCH ROADS, REPLACE BOC WITH EOP (EDGE OF PAVEMENT). THE X-4-18 IS A 18"X18"
0.063 GAUGE ALUMINUM PANEL
COVERED WITH RED HIGH
INTENSITY REFLECTIVE SHEETING.



CHRIS E. BAUSERMAN, P.E., P.S. Delaware County Engineer

Delaware County Engineer

APPROVED 1-22-2008

-2008 REVISED 1-04-2010

STANDARD CONSTRUCTION DRAWING

TEMPORARY BARRICADE FOR END OF ROADWAY PAVEMENT

DELAWARE COUNTY ENGINEER'S OFFICE 50 Channing Street Delaware, Ohio 43015

PHONE: **(740)833–2400** FAX: (740)833–2399

www.	.co.del <mark>aware.</mark>	oh.us	

Drawn	KS	sheet	1	FILE NO.
 Checked_	EM	of _	1	DCED-R2190