



* PLATE AND BAR HAVE BEEN SIZED BASED ON STANDARD STEEL EXPANSION JOINTS. CONTRACTOR SHALL VERIFY DIMENSIONS FOR EACH INSTALLATION. PLATE AND BAR SHALL BE 1/2" LESS IN WIDTH THAN THE EXISTING CONDITIONS.

THIS ITEM SHALL INCLUDE FURNISHING OF ALL MATERIALS AND NECESSARY LABOR TO FABRICATE, ASSEMBLE, CONSTRUCT AND INSTALL VERTICAL EXTENSIONS. ALL COSTS TO BE INCLUDED IN THE CONTRACT BID PRICES FOR ITEM 516 VERTICAL EXTENSION OF STRUCTURAL EXPANSION JOINTS PER LINEAR FOOT INSTALLED. ITEM 516 OF THE CURRENT COLUMBUS CONSTRUCTION AND MATERIAL SPECIFICATIONS SHALL GOVERN THE ITEMS OF THIS WEEK.

NOTE: IF ANY PORTION OF EXPANSION JOINT IS OPENED TO TRAFFIC PRIOR TO PAVING OPERATIONS, A TEMPORARY ASPHALT RAMP SHALL BE CONSTRUCTED.

CHRIS E. BAUSERMAN, P.E., P.S.
Delaware County Engineer

Chris Bauserman
Delaware County Engineer

STANDARD CONSTRUCTION DRAWING
VERTICAL EXTENSION OF
STRUCTURAL EXPANSION
JOINTS
ITEM 516

DELAWARE COUNTY ENGINEER'S OFFICE
50 Channing Street
Delaware, Ohio 43015
PHONE: (740)833-2400 FAX: (740)833-2399
www.co.delaware.oh.us

APPROVED
1-22-2008

REVISED

Drawn KS
Checked EM

sheet 1
of 1

FILE NO.
DCED-R2347