



NOTES:

1. Backfill of trench from top of #57 Crushed Stone Bedding to the top of trench shall be Compacted to 95% maximum dry density in accordance with current County Standards. No grits will be allowed.
2. The compaction requirement will be strictly enforced by the County.
3. The ℄ of the proposed storm sewer should be offset from the property line.
4. The cost of the #57 Crushed Stone Bedding, Compacted Fill and Backfill shall be included in Item 901.
5. Minimum width of trench and quantities used shall be per Standard Drawings DCED-S149, DCED-S151 or DCED-S152.

<p>CHRIS E. BAUSERMAN, P.E., P.S. Delaware County Engineer</p> <hr/> <p><i>Delaware County Engineer</i></p>	<p>STANDARD CONSTRUCTION DRAWING</p> <p>TYPICAL TRENCH DETAIL FOR RIGID STORM SEWERS OUTSIDE R/W WITH COVER 30" OR LESS</p>	<p>DELAWARE COUNTY ENGINEER'S OFFICE 50 Channing Street Delaware, Ohio 43015 PHONE: (740)833-2400 FAX: (740)833-2399 www.co.delaware.oh.us</p>	
<p>APPROVED 1-22-2008</p>	<p>REVISED 1-04-2010</p>	<p>Drawn <u>KS</u> sheet <u>1</u> Checked <u>EM</u> of <u>1</u></p>	<p>FILE NO. DCED-S155</p>