ITEM SPECIAL - MAILBOX AND SUPPORT, AS PER PLAN

THIS WORK SHALL CONSIST OF FURNISHING TEMPORARY MAILBOXES AND RE-ERECTING EXISTING MAILBOXES AND SUPPORTS AND ANY ASSOCIATED MOUNTING HARDWARE IN ACCORDANCE WITH PLAN DETAILS AT LOCATIONS SPECIFIED IN THE PLAN, OR OTHERWISE ESTABLISHED BY THE ENGINEER.

THE CONTRACTOR SHALL REMOVE AND STORE THE EXISTING PERMANENT MAILBOXES AND SUPPORTS ONSITE IN A SAFE MANNER. THIS CAN BE DONE BY BUILDING A RACK SYSTEM, TEMPORARY HOLDING SYSTEM, OR OTHER MEANS. LAYING MAILBOXES ON THE GROUND WILL BE AN UNACCEPTABLE MANNER. ALL SHALL BE STORED IN THE CONTRACTOR AREA. THIS IS MEANT TO MAINTAIN THE INTEGRITY OF THE MAILBOX BEFORE CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE AND INSTALL TEMPORARY MAILBOXES FOR ALL RESIDENTS, ALONG WITH THE ADDRESS MARKINGS, TO BE USED DURING CONSTRUCTION. AFTER CONSTRUCTION IS COMPLETE THE CONTRACTOR IS TO REINSTALL THE PERMANENT EXISTING MAILBOX WITH ITS CURRENT POST IF IN GOOD SHAPE OR REPLACE THE POST WITH A SIMILAR POST THAT WAS REMOVED.

IF A POST NEEDS REPLACED IT SHALL BE SIMILAR TO THE EXISING TYPE. THE STANDARD WOOD POSTS SHALL BE NOMINAL 4 INCHES BY 4 INCHES SQUARE OR 4.5 INCHES DIAMETER ROUND AND CONFORM TO 710.14.

STELL POSTS SHALL BE NOMINAL PIPE SIZE 2 INCHES I.D. AND CONFORM TO AASHTO M 181.

ALL HARDWARE INCLUDING BUT NOT LIMITED TO PLATES, SCREWS, BOLTS, AND ETC. SHALL BE COMMERCIAL – GRADE GALVANIZED STEEL.

POSTS SHALL BE SET PER 606.03 AND SHALL IN NO INSTANCE BE ENCASED IN CONCRETE.

SUPPORT HARDWARE SHALL ACCOMMODATE EITHER A SINGLE OR A DOUBLE MAILBOX INSTALLATION, AND NO MORE THAN TWO BOXES MAY BE MOUNTED ON A SINGLE POST.

THE MAILBOX SHALL BE SECURELY AND NEATLY ATTACHED BY THE CONTRACTOR TO THE NEW SUPPORT. THE CONTRACTOR SHALL FURNISH ALL NECESSARY ATTACHMENT HARDWARE (NUTS, BOLTS, PLATES, SPACERS, AND WASHERS) AS NECESSARY TO ACCOMMODATE THE COMPLETE INSTALLATION.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING WITH THE LOCAL POSTMASTER REGARDING THE TIMING OF THE MOVEMENT OF ANY MAILBOX TO A NEW LOCATION.

PAYMENT UNDER THIS ITEM SHALL BE FOR THE FINAL PERMANENT INSTALLATIONS AS WELL AS THE TEMPOARY BOXES. TEMPORARY INSTALLATIONS SHALL BE IN ACCORDANCE WITH 107.10. HOWEVER, THE SAME MATERIAL AND SIZE LIMITATIONS AS FOR PERMANENT INSTALLATIONS SHALL APPLY.

MAILBOX AND SUPPORTS, COMPLETE IN PLACE, WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER EACH, FOR ITEM SPECIAL MAILBOX AND SUPPORT SYSTEM, (SINGLE) (DOUBLE), AS PER PLAN.

THE FOLLOWING QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY:

ITEM SPECIAL – MAILBOX AND SUPPORT, AS PER PLANS

XX EACH